



NOTES

1. ALL GROUNDING POINTS SHALL BE TIED TOGETHER.
2. GROUND RODS: 5/8" x 8'-0" COPPER CLAD STEEL WITH 25 OHM OR LESS RESISTANCE (3 MIN. REQUIRED)
3. GROUND WIRE: NO. 6 BARE SOLID COPPER WIRE
4. CONTRACTOR SHALL PROVIDE GROUNDING TEST RESULTS TO THE CITY.



HISTORIC
FRANKLIN
TENNESSEE

TRAFFIC SIGNAL CABINET GROUNDING

CITY OF FRANKLIN

NOT TO SCALE

CITY
ENGINEER:

Paul P. Hoyle

DATE:

7/1/2021

DWG. NO.

ITS-4