



APPROVED MANUFACTURERS:

1. QUAZITE
2. MARTIN ENTERPRISES
3. ARMORCAST

NOTES:

- 1) EXCAVATE AND BACKFILL WITH MINIMUM EIGHTEEN INCH (18") THICK LAYER OF #57 CRUSHED GRAVEL.
- 2) INSTALL BOX AND BACKFILL TO WITHIN TWELVE INCHES (12") OF FINISHED GRADE WITH #57 CRUSHED GRAVEL.
- 3) BACKFILL INSIDE BOX WITHIN THREE INCHES (3") OF THE TOP OF THE CONDUIT WITH #57 CRUSHED GRAVEL.
- 4) THE TOP OF THE PULL-BOX MUST BE FLUSH WITH FINISHED GRADE.
- 5) PULL-BOX TO BE FURNISHED AND INSTALLED BY CUSTOMER.
- 6) SCHEDULE INSPECTION OF PULL-BOX INSTALLATION WITH CITY OF FRANKLIN STREET DEPARTMENT A MINIMUM OF THREE BUSINESS DAYS PRIOR TO INSPECTION.
- 7) CITY OF FRANKLIN RESERVES THE RIGHT TO REQUIRE A LARGER PULL-BOX. IF LARGER PULL-BOX IS REQUIRED, THE CITY WILL ISSUE SPECIFICATIONS AND INSTALLATION REQUIREMENTS FOR THE LARGER PULL-BOX.
- 8) PULL-BOXES ARE REQUIRED TO BE INSTALLED AT THE MIDPOINT OF ANY CIRCUIT RUN THAT EXCEED 300 FEET
- 9) PULL-BOXES ARE NOT TO BE INSTALLED IN THE PATH OF VEHICLAR TRAVEL.
- 10) PULL-BOXES SHALL BE UL LISTED.

N.T.S



HISTORIC
FRANKLIN
TENNESSEE

STREET LIGHT LARGE PULL BOX INSTALLATION DETAIL

CITY OF FRANKLIN
NOT TO SCALE

CITY
ENGINEER:

Paul P. Hoyle

DATE:
7/1/2021

DWG. NO.

L-10